License# A2ZRORL835PQ

Customer Name:	Adam Cobb			***Date:***	October 4, 2026
Contact Name:				***Contact Number:***	0
Address:	14211 Serene Way			***Cell Number:***	0
City:	Lynnwood	***Zip:***	98087	***Fax Number:***	0

A2Z ROOFING LLC "BID PACKAGE"

Scheduling of work & deliveries: Three day notice of work to begin will be given if allowed. Upon the scheduling of work, we will start, weather permitting. ***PLEASE READ THINGS TO CONSIDER ONCE WE MAIL YOU SCHEDULE DATE...***

Protection of Property: The crew will begin with designing a plan to protect the outside of your home. This may include tarps, plywood and plastic but not limited to these items. There will be a definite emphasis placed on protecting your home. We will take every precaution to protect your ***PLANTS*** and ***SHRUBBERY.***

Tear off: **Remove existing roof system (noted below)** shingles, all nails, metals, counter flashing, etc., as necessary to prepare for installation of new roof system. Then inspect the roofs sub structure for rotten or damaged pieces to ensure a solid nailing surface for new roofing system. During the tear off portion of the re-roof, siding can get damaged due to lack of maintenance, degradation of fibers in siding i.e. Fiber Cement, LP or Masonite, Any repair to siding or sub structure see T-M section below, unless noted in proposal.

We found the following layers on your roof ***1*** ***ea***

All unforeseen layers other than stated above: Will be removed for an additional amount of $ 100.00 per square. (10x10)

Time and Materials **:** Any additional work not outlined in this proposal will be billed on a time plus material basis, ($64.00/man hour that will include drive time and WSST). Additional work to install roof to current standards, or to remedy structural inadequacies that may include: DRY ROT, DELAMINATING PLYWOOD. BROKEN SKIP SHEETING, ROTTEN FASCIA BOARDS AND RAFTER TAILS, DAMAGED SIDING, SHEETROCK, STUCCO, MASONRY OR PLASTER AS A RESULT OF THE ROOFING PROCESS.

Beaded soffit /shiplap priced at 8.75/ lft Plywood replacement at 100.00 a sheet.(On buildings with existing plywood !)

Underlayment: ***Synthetic underlayment*** required for vapor barrier over sheeting.

Eave flashing/ Gutter Edge: **3" x 1"** prepainted baked on enamel ***26*** gauge metal.

Rake flashing/ Gable End: **1.5" x 1.5"** prepainted baked on enamel **26** gauge metal (color) - _____ Int.

Starter shingle: Install starter shingle system per manufacturer specifications and requirements

Valley flashing: **24" W -Valley** shaped prepainted **26** gauge metal.

Chimney flashing: Replace all **(Step-flash / 3x5 roof to wall / Chimney Pan)** with prepainted/ enamel **26** gauge metal.

Bathroom / Kitchen vent: **RCV- 4" and 6" vents** to exhaust moist air from home.

Plumbing Pipes: Replace all **pipes boots** with No Caulk pipe flashings**.**

Hot water / heater vent flashing: Replace all **base flashing /collars and paint entire stack** to match shingle color. Any work required with actual vent operation MUST be done by an approved HVAC installer and will be billed at T-M.

Exhaust venting system: We will Install ***8*** ea AF 50 **Vents** to meet code.

Leak barrier: Install a **2'x2' patch at all penetrations** through the roof to provide additional protection.

Pick from: _____ Pabco- _____ Initial

Type/Style: _____ ***Color:*** _____

Hip/Ridge Shingles: ***Upgraded High Profile H n R Shingles (Standard) on all premium roof shingle applications***

Fasteners / Nails: ***G*** **alvanized roofing nails** with 3/8" head diameter; minimum 11 or 12 gauge

A2Z ROOFING WILL ALWAYS NAIL TO HIGH WIND SPECIFICATION, (6) NAILS PER SHINGLE

Clean up: upon completion of work, we will remove all tools, equipment and surplus material leaving the premises in a broom clean condition. Then a final sweep of the premises will be made with the **roller magnet to remove the nails**.

Safety anchor: *Install* ***(1) permanent safety anchor in ridge*** *for future maintenance(Fall restraint only)*

NOTES:

Roofing Products	Initials	
Pabco Premier		**$ 11,402**
Extras & Accessories	Initials	
Seamless 5" K style gutters with downspouts (Includes Tear Off) Color White		**$ 3,148**

*****Above prices do not include additional Washington State Sales Tax*****

Workmanship: Work orders are to be completed to meet codes regulating the demolition, repair and or replacement of all work performed.

Acceptance: 20% will be due on day of agreement. Balance is paid to Quality Control/ Forman or Sales person upon completion of the project. Items that will be billed and/or paid as separate items will include: ***ALL non-roofing trade labor, gutters, skylights Permits and ALL Time and Material items. This will be invoiced within two days of completion and will include a detail of what work has been done and the time to accomplish.***

Financing must be done before job can be scheduled!
All credit card payments subject to convenience fee of 3.5%.

We propose the above specified work for: **Plus tax**

Payment terms: PAYMENT IN FULL UPON COMPLETION AND INSPECTION

Signature: _____ Professional _____
Authorized Purchaser — Authorized consultant

Date: _____ Date: _____

The prices, specifications and conditions on the proposal are satisfactory and hereby accepted. Payment terms are 20% upon signing contract and remainder due upon completion unless other arrangements are made. Proposal does not include permits or tax's.

Owner: Jimmie Fick

Contact #: 206 799 5229

Proposal Good for 45 Days