Wu Construction, Inc.

Wu Construction, Inc.
(206) 361-8886
drainagepeople.com
LIC. #WUCONCI892Q9
wuconstruction@gmail.com

Order# 14211
Date: October 7, 2026
Property:
14211 Serene Way Lynnwood, WA 98087

Office Use Only:
Contact Information:
Name: Lindsey Lundberg
Phone: 425-563-3136
Email: lindseylundberg@windermere.com

Proposed Estimate:	Amount
1. Install an interior full crawl space perimeter below footing drainage system with perforated pipe and drainage gravel (French drain) 2. Install an interior 1/3 hp sump pump assembly 3. 1 ½" ABS pipe discharge to drywell or existing functioning drain 4. Clean up crawl space and remove debris 5. Replace and install a new 6 mil black vapor barrier 6. Replace all subfloor insulation with R30 7. Insulate the water line 8. Install a new crawl space access door with ¼" open mesh and pressure treated wood 9. Install a new crawl space access hatch 10. Check and seal visible entry points to prevent rodent entry Ongoing immediate pest management is advised (by a pest control company) because rodents are very common in the area	(1-3) $4,950.00 (4-9) $7,750.00 (10) $0.00
Subtractions/Discounts/Credits	
Subtotal:	$12,700.00
Tax:	$1,358.00
Total:	**$14,058.00**

Notes:
Lockbox code: [redacted]
*If there is an existing/non-existing gravity drain outlet option, we will exercise that option for the same price versus the sump pump
Estimate based on the crawl space being at least 24" high, dirt crawl space with no iron oxide in the ground water

Warranty:
Wu Construction provides a 25-year **transferable** warranty on the entire installed drainage system on the **property**. The sump pump, if applicable, has a one-year service warranty. If there happens to be new water intrusion in the area where the footing drainage was installed, there will be no charges to the owner, if the water intrusion is a result of our drainage system failing.
Our guarantee is that there is no water intrusion in the area where the drainage system was installed.
We have been licensed, bonded, and insured since 1983. Thank you for your business!

Thomas Wang
Vice President
Wu Construction Inc
Direct: (206) 786.1024
Office: (206) 361-8886
thomjwang@gmail.com